

Prefabricated POP



A prefabricated POP is a defined concrete construction according to the customer's specifications. The POP can be supplied in 3 sizes. Each type will have a basic lay-out, with all internal walls finished. All technical installations installed. ODF frames installed, equipment frames installed, air-condition installed, UPS installed. The cover of the outer wall will be according the specifications in the building permit.

Features

- Construction is done in the workshop of the supplier
- Building space at construction site is limited
- Building time is reduced.
- Ordering process simple.
- Standardisation of Network buildings

Material

- Concrete
- Finishing of outer wall according to specifications in the building permit

Note

Prefabricated POP requires details engineering for each new customer

Types

| | Ordering code |
|-------------------------------------|---------------|
| Prefabricated POP, 15m ² | |
| Prefabricated POP, 27m ² | |

Dimensions

| | 7.5m ² | 15m ² | 27m ² |
|---------|-------------------|------------------|------------------|
| Height: | 3.62m | 3.77m | 3.52m |
| Width: | 2.70m | 2.98m | 2.98m |
| Length: | 2.70m | 4.78m | 8.98m |
| Weight: | 16.500 kgs | 27.000 kgs | 50.000 kgs |

© PRYSMIAN GROUP 2012, All Rights Reserved

All sizes and values without tolerances are reference values. Specifications are for product as supplied by Prysmian Group: any modification or alternation afterwards of product may give different results. The information claimed within this document must not be copied, reprinted or reproduced in any form, either wholly or in part, without the written consent of Prysmian Group. This information is believed to be correct at the time of issue. Prysmian Group reserves the right to ammend this specification without prior notice. This specification is not contractually valid unless specifically authorised by Prysmian Group.

Prefabricated POP

Sample Floorplan Prefabricated POP 15m²

